

	TEMPORARY TRAFFIC CONTROL					
	TEMPORARY TRAFFIC CONTROL					
PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	UNIT PRICE	TOTAL PRICE	
	SPECIAL DETOUR- TEMPORARY PAVEMENT SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE	SY CY	4000 1900		\$ \$	99,960.00 65,949.00
102-14	TRAFFIC CONTROL OFFICER	HR	930	\$ 57.15	\$	53,149.50
	WORK ZONE SIGN	ED	40530		\$	8,511.30
	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE TEMPORARY BARRIER, RELOCATE, LOW PROFILE, CONCRETE	LF LF	2600 1325		\$ \$	184,574.00 8,811.25
	CHANNELIZING DEVICE-TYPES I, II, DI, VP, DRUM, OR LCD CHANNELIZING DEVICE-PEDESTRIAN LCD	ED FD	328080 30600		\$ \$	32,808.00 918.00
102-76	ARROW BOARD/ADVANCE WARNING ARROW PANEL	ED	600	\$ 5.24	\$	3,144.00
102-99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1200		\$	11,760.00
102-115	TYPE III BARRICADE	ED	11610	\$ 0.26	\$	3,018.60
			SIGNALIZAT	ION SUBTOTAL:	\$	472,603.65
	SIGNING AND PAVEMENT MARKING					
706-1-3	RAISED PAVEMENT MARKER, TYPE B	EA	1,281	\$ 4.41	\$	5,649.21
10-11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID 6" PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE, 24"	GM LF EA EA	9 275		\$ \$	13,019.68 448.25
110-11-170	PAINTED PAYEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL PAINTED PAYEMENT MARKINGS, STANDARD, WHITE, ARROWS PAINTED PAYEMENT MARKINGS, STANDARD, YELLOW, SOLID 6"	EA EA GM	4 26 8	\$ 50.43 \$ 35.36 \$ 1.480.15	\$ \$	201.72 919.36 12.359.25
710-11-224	PÄINTED PÄVEMENT MARKINGS, STÄNDARD, YELLOW, SÖLID FOR DIAGONAL OR CHEVRON 18"	LF	284	\$ 1.69	š	479.96
		SIGNING	AND PAVEMI	ENT SUBTOTAL:		33,077.44
101-1	MOBILIZATION	LS	1	SUBTOTAL: 5%		505,681.09 25.284.05
	CONTINGENCY	LS	1	20% GRAND TOTAL:	\$	101,136.22 632,101.36

SOURCE: FDOT Historical Costs - Area 8

NOTE:

1. Cost opinion based on assumed construction durations for each phase. Actual duration of each phase to be determined by the contractor.

2. Quantities shown for TTC devices, pavement markings, and TCOs are approximate and are subject to change. Final quantities to be determined by the contractor.

3. Quantities shown for temporary pavement and earthwork are approximate based on roadway and TTC plans and are subject to change depending on conditions in the field.